



Pallet Quantities

NOMINAL PIPE SIZE	FEET PER BUNDLE	
C900 & C905	20'	
4"	960	
6"	560	
8"	200	
10"	160	
12"	60/80/120/160	
14"	120	
16"	40/60/80/120	
18"	80/120	
20"	80	
24"	60	
30"	60	
36"	40	
Gravity Sewer D3034/F679	14'	20'
4"	924	1,320
6"	462	660
8"	420/504	600/720
10"	168	240
12"	224	320
15"	84	120
18"	28/42/56/84	40/60/80/120
21"	56	80
24"	56	80
27"	42	60
30"	42	60
36"	28	40
IPS D2241	20'	
1/2"	8,100	
3/4"	4,800	
1"	3,000	
1 1/4"	4,780	
1 1/2"	6,300	
2"	4,080	
2 1/2"	2,700	
3"	1,760	
3 1/2"	1,260	
4"	1,140	
5"	760	
6"	520	
8"	280	
10"	240	
12"	80/160	
14"	120	
16"	120	
18"	40/60/80/120	
Sewer & Drain D2729	10'	
3"	880	
4"	660	
6"	330	
CPVC-CTS	10'	
1/2"	500	
3/4"	240	

NOMINAL PIPE SIZE	FEET PER BUNDLE	
Sch 40 & Foam Core ABS & PVC	10'	20'
1/2"	4,050	8,100
3/4"	2,400	4,800
1"	1,500	3,000
1 1/4"	1,960	3,920
1 1/2"	3,150	6,300
2"	2,100	4,200
2 1/2"	1,350	2,700
3"	920	1,840
4"	570	1,140
5"		760
6"	240	480
8"	140	280
10"	120	240
12"	40/80	80/160
14"		120
16"		120
18"		40/60
20"		40
24"		40
Sch 80	20'	
1 1/2"	6,300	
2"	4,200	
2 1/2"	2,700	
3"	1,840	
4"	1,140	
5"	760	
6"	480	
8"	280	
10"	240	
12"	80/160	
Well Casing	20'	
2"	4,080	
2 1/2"	2,700	
3"	1,760	
3 1/2"	1,260	
4"	1,140	
4 1/2"	860	
5"	760	
6"	520	
6 1/8"	400	
6 1/4"	400	
8"	280	
10"	240	
12"	80/160	
14"	120	
16"	60/120	
Sch 30	10'	
3"	880	